Division 8 – Openings

- 08.1. General
 - a. Doors and hardware are to be coordinated with the requirements of the SECURITY SECTION IN CHAPTER THREE of these standards and APPENDIX T-ELECTRONIC ACCESS CONTROL & CONDUIT DIAGRAMS.
 - b. The A/E shall specify all hardware in a separate hardware section. Storefront door hardware shall be included in this hardware section and not in the storefront specification.

08.2. Exterior Building Entry Doors

- The A/E shall consider wind direction, microclimate conditions and wind pressures when designing building entrances. Entry doors in the north and east facades of buildings are subject to high winds. Consider ways to provide windscreens for all exterior doors, but especially the north and east.
- b. All exterior building entries shall be arranged using a vestibule or "airlock" to avoid excessive exchange of conditioned indoor and unconditioned outdoor air.

08.3. Interior Doors

- a. Clear glazed vision panels shall be used in all classroom and stair doors.
- b. When double doors are necessary at card access locations, provide a removable mullion.

c. Wood doors shall be solid core and shall be reinforced for all hardware including closers; prime or seal all hardware cut outs and top and bottom of door. All

- a. In general window frames shall be thermally broken 2" x 4-1/2" heavy commercial aluminum windows, flush dry glazed from the interior.
- b. In residence halls, if fiberglass windows are being considered as a design option, discuss with the Department of Design and Construction during schematic design.
- c. Prior to acceptance by the University, proposed manufacturers must provide to the ODU Project Manager copies of test reports by an independent laboratory which certify the proposed window unit's performance standard baseline. The test reports will identify the standards used and provide documentation of those standards.
- d. Written guarantee shall state that all components will meet specified performance requirements for a period of 2 years following acceptance and that defects will be repaired during the term of the guarantee at no cost to the University
- e. Weather stripping shall be shall be guaranteed for a period of 5 years.
- f. Standard finish colors are clear anodized, powder coated silver, white or steel gray (College of Education). Custom Colors are to be approved by the university.
- g. All pre-finished windows shall have protective coverings during construction, until units are installed.
- h. Window selection shall consider the window styles of surrounding buildings and visually adjacent windows.
- i. In residence halls, all operable windows on the first floor shall have security screens.

08.12. Sun Shades

a. The design shall incorporate sun shade devices as appropriate for the sun angles on each specific elevation. Sun shade devices should not be added to windows on elevations where the impact is minimal. Consider vertical shading devices on east and west facades. Provide a sun study of the building exterior during schematic design demonstrating the impact of the shading devices on the glass, estimate the percentage area of glass shaded by these devices for June and December at 8 a.m., noon and 5 p.m.

08.13. Metal Framed Skylights

- a. Skylights shall not be used in any occupiable spaces, including corridors.
- b. Solar tubes are acceptable.

08.14. Door Hardware

- a. Pre-wire / pre-drill all potential card access doors.
- b. All doors and frames shall be prepped by the manufacturer for all hardware to be provided by the University.
- c. Provide at least one key override on an exterior door in each building. Provide rim cylinder only with night latch trim, pull handles.
- d. During the working drawing phase, the A/E shall meet with the ODU Project Manager, the FM lock shop supervisor and ITS access control to review the program needs for locks and hardware in the proposed project, using the security and access plan developed during schematic design as the discussion guide.
- e. A first pass of the door hardware schedule and hardware specifications is required at 60% Working Drawings Progress review. The ODU Project Manager will set up a separate hardware meeting with the Lock Shop Supervisor, representatives of the building users along with ITS and Public Safety/Campus Security to review the hardware design. As stated previously in these standards, but reinforced here,

building room numbers are to have been finalized and approved by the University Space Manager, prior to this meeting.

- f. The A/E shall specify all required hardware for each opening. One manufacturer shall be scheduled with two other acceptable manufacturers listed. All hardware shall be approved by the University. A complete hardware schedule and full set of specifications is required at the owner review working drawing submission, which is prior to BCOM Working Drawing submission.
- g. Prior to shop drawing submission, a hardware coordination meeting is to be scheduled by the general contractor to include the ODU project manager, the A/E, user groups, ITS and the Facilities lock shop to discuss project specific issues related to lock functions, coordination and delivery. The Contractor shall prepare the final keying schedule based on this meeting that clearly indicates how the University's final instructions on keying of locks has been fulfilled and submit it as part of the hardware submittal process.
- h. The General Contractor shall procure all cylinders and cores and install same. Construction cores may be installed by the contractor during construction, but shall be removed prior to beneficial occupancy.
- i. Furnish three (3) keys per lockset or as directed by the ODU Project Manager.
- j. Single Source Responsibility: Obtain each type of hardware latch and locksets, hinges, closers, etc. from a single manufacturer.
 - i. Hardware Finishes:
 - The designations used to indicate hardware finishes are those listed in ANSI/BHMA A156.18, "Materials and Finishes," including coordination with the traditional U.S. finishes shown by certain manufacturers for their products.
 - a. Continuous Hinges: 628 (US28) Clear Anodized Aluminum
 - b. Door Closers: 689 Powder Coat Aluminum
 - c. Door Stops: 626 (US26D) Satin Chrome Plated Brass/Bronze
 - d. Exit Devices: 626 (US26D) Satin Chrome Plated
 - e. Flush Bolts: 626 (US26D) Satin Chrome Plated Brass/Bronze
 - f. Hinges (Exterior): 630 (US32D) Satin Stainless Steel
 - g. Hinges (Interior): 626 (US26D) Satin Chrome Plated Steel
 - h. Locks: 630 (US32D) Satin Stainless Steel
 - i. Overhead Holders: 630 Satin Stainless Steel
 - j. Protective Plates: 630 (US32D) Satin Stainless Steel
 - k. Pull Plates: 630 (US32D) Satin Stainless Steel
 - ii. Heavy Weight and Standard Weight Hinges:
 - iii. Concealed Bearing 5 Knuckle Full Mortise Hinges.
 - iv. Lifespan Bearing System
 - v. Painted Hinges are not acceptable.
 - vi.v. Non-removable pins (NRP) All locations
 - vii.vi. Concealed Electric Hinges
 - 1. Heavy Weight
 - 2. Concealed Bearing 5 Knuckle Full Mortise Hinge
 - 3. Concealed wires
 - 4. Concealed switches
 - 5. Shop weld junction box before frame is set

ii. 5/8" x 1-3/8" x 2-7/8" bolt with a 1-3/8" throw made of eight ply laminated stainless steel.
Center ply to be an alumina-cerami

- 2. If there are a series of doors, both doors in the series must have automatic openers. Each door shall open independently.
- 3. Automatic Door Operators and switch shall be hard-wired into the emergency circuit and be provided with battery backup.
- 4. Field adjustable
- 5. Adjustable Spring Force
- 6. Non Handed
- 7. Full or low energy
- 8. Acts as a mechanical closer for manual operation in the event power is off.
- 9. Controller configuration via Bluetooth Technology

xxvi. xxv.	_Gaskets
	1. All classroom doors shall receive screw on sound gaskets (no self-adhesive)
xxvii. xxvi.	_Automatic Door Bottoms
	1. Are acceptable
xxviii. xxvii.	_Rain Drip guards
	1. Provide 1 ½" high x 2 ½" deep (min) rain drip guard in clear anodized at all exterior doors
	that are installed in a flush application (i.e. without any building overhang).
xxix.<u></u>xxviii.	_ Electromagnetic Door Holders
	1. Recessed wall mount or surface wall mount depending on application.
	2. Reinforce Door at hold open.
xxx. xxix.	Long Door Pulls
	1. Provide a contrasting finish in the grip zone.
	2. 1" Diameter
	3. Offset Pulls with round ends
xxxi. xxx.	_Networked Hardwired electronic Locks